


DETAIL OC. KONZOLY MARKIZY / KRAJNYCH/ M 1:10



DETAIL OC. KONZOLY MARKIZY / STREDNEJ/ M 1:10

OC. MATERIAL - 3KS KONZOL MARKIZY:

| MATERIAL                                 | POET KUSOV | DLZKA 1KS/M | DLZKA CELKOM | HMOTNOST |
|--|------------|-------------|--------------|----------|
| JACKLOVY PROFIL 30/30/2.5MM DL. 1540MM   | 2          | 1,54        | 3,08         | 6,652    |
| JACKLOVY PROFIL 30/30/2.5MM DL. 1434MM   | 2          | 1,434       | 2,868        | 6,195    |
| TYCOVINA Ø 12MM                          | -          | -           | 1,99         | 0,884    |
| KOTIVACA PASOVINA 100/450/8MM            | 3          | 0,45        | 1,35         | 8,208    |
| TENKOSTENNY PROFIL 150/20/2MM DL. 2250MM | 2          | 2,25        | 4,50         | 4,425    |
| JACKLOVY PROFIL 50/20/2MM DL. 2250MM     | 2          | 2,25        | 4,50         | 9,315    |
| TENKOSTENNY PROFIL 150/20/2MM DL. 1540MM | 2          | 1,54        | 3,08         | 3,234    |
| JACKLOVY PROFIL 50/20/2MM DL. 1540MM     | 2          | 1,54        | 3,08         | 6,37     |
| VZPERA - PASOVINA 100/305/5MM /UPRAVENA/ | 2          | 0,35        | 0,70         | 4,123    |
| JACKLOVY PROFIL 30/30/2.5MM DL. 1612MM   | 1          | 1,612       | 1,612        | 3,482    |
| JACKLOVY PROFIL 30/30/2.5MM DL. 1504MM   | 1          | 1,504       | 1,504        | 3,248    |
| VZPERA - PASOVINA 100/321/5MM /UPRAVENA/ | 1          | 0,321       | 0,321        | 3,781    |
| LEXAN THERMOCLEAR                        | 1          | -           | 3,50m²       | -        |
| HMOTNOST V KG CELKOM:                    |            |             |              | 54,917   |


POZNAMKA:

POVRCHOVA UPRAVA OCELOVYCH KONZOL BUDE PREVEDENA ZIAROVYM-ZINKOVANIM, AKO CELY KUS.  
OCELOVE TENKOSTENE JACKLOVE PROFILY BUDU PRED ZINKOVANIM OPATRENE NAVRTANIM OTVOROV, PRE PRETECENIE ZINKOVANIA.  
OTVORY PREVIEST PRI KOTIVACICH PASOVINACH OTVOR Ø10MM.





±0,000 = JESTVLICE

AUTORIZACIA:

INVESTOR :  
SOCIALNA POISTOVNA - USTREDE  
UL. 29.AUGUSTA c.8 A 10, 813 63 BRATISLAVA

  
SOCIALNA POISTOVNA  
REKONSTRUKCIA VYTAHU

NAZOV STAVBY:  
SOCIALNA POISTOVNA - USTREDE, BRATISLAVA  
REKONSTRUKCIA VYTAHU



VPU DECO BRATISLAVA a.s., ZA KASARNOU 1, 831 03 BRATISLAVA, www.vpu deco.sk

ZODPOVEDNY PROJEKTANT:  
INGARCH M. DVORSKY

MIERKA:  
1 : 50

C. PARE :  
C. PARE :

HLAVNY KOORDINATOR  
ING. IGOR TOH

DATUM :  
08 / 2016

VYPRACOVAL:  
Frontisek BOJANOVSKY

FORMATY :  
2 x A4

VYSTUPNA KONTROLA:  
INGARCH M. DVORSKY

C. ZAKAZKY:  
16023 009

OBJEKT:  
01 - REKONSTRUKCIA VYTAHU

STAVEBNE RIESENIE

PROFESIA:  
NAZOV PRILOHY:

STUPEN  
DRS

DIEL  
E01

C. PRILOHY  
7